PROPERTY CONDITION ASSESSMENT

Cypress Commons | Las Vegas, NV

Property	Cypress Commons
Address	6461 Railroad Boulevard, Las Vegas, NV 23840
Site Visit Date	December 23, 2022
Client	Tidewater Core Fund
Immediate Repairs	$137,000

Construction Details

The structure is of wood-frame, masonry and steel-frame construction on a slab-on-grade foundation. Mechanical systems include rooftop package units and central plant equipment of varying age. Exterior finishes comprise brick veneer, fiber-cement siding and aluminum storefront glazing in good condition. Average in-place rent is $1,279 per month against an average unit size of 973 square feet. Unit interiors feature quartz countertops, stainless appliances, in-unit washer and dryer and plank flooring in select renovated homes. Resident turnover has averaged 2.3% annually with renewal retention above 88.2%.

The community offers a resort-style pool, fitness center, resident clubhouse, package lockers and a dog park. Cypress Commons was originally constructed in 1969 and consists of 416 apartment homes in a building of 6 stories. Life-safety systems include a fully sprinklered building, addressable fire alarm panel and emergency lighting. Common area interiors have been refreshed within the last 12 years and are in average to good condition.

Deferred Maintenance

ADA observations include non-compliant slopes at two accessible routes and signage at parking; cost to cure is estimated at $81,000. Domestic water piping is copper and PVC with no evidence of widespread leakage. Electrical service is adequate for current demand; select panels are nearing the end of their useful life. The roofing system exhibits localized ponding and sealant deterioration; spot repairs are recommended within 12 months. Asphalt paving shows alligator cracking and should be sealcoated and restriped during the next 37 months.

Windows and exterior doors are in fair condition; sealant replacement is recommended at selected locations. Electrical service is adequate for current demand; select panels are nearing the end of their useful life. ADA observations include non-compliant slopes at two accessible routes and signage at parking; cost to cure is estimated at $255,000. The roofing system exhibits localized ponding and sealant deterioration; spot repairs are recommended within 12 months. Domestic water piping is copper and PVC with no evidence of widespread leakage. Elevators were last modernized 8 years ago and are operating without deficiency.

Improvements Description

Mechanical systems include rooftop package units and central plant equipment of varying age. Exterior finishes comprise brick veneer, fiber-cement siding and aluminum storefront glazing in good condition. The roof is a 9-year membrane system with an estimated remaining useful life of 6 years. Resident turnover has averaged 4.2% annually with renewal retention above 92.9%. The community offers a resort-style pool, fitness center, resident clubhouse, package lockers and a dog park. Unit interiors feature quartz countertops, stainless appliances, in-unit washer and dryer and plank flooring in select renovated homes.

Unit interiors feature quartz countertops, stainless appliances, in-unit washer and dryer and plank flooring in select renovated homes. Cypress Commons was originally constructed in 1969 and consists of 416 apartment homes in a building of 8 stories. Common area interiors have been refreshed within the last 8 years and are in average to good condition. The structure is of wood-frame, masonry and steel-frame construction on a slab-on-grade foundation. Life-safety systems include a fully sprinklered building, addressable fire alarm panel and emergency lighting.

Observed Conditions

Asphalt paving shows alligator cracking and should be sealcoated and restriped during the next 31 months. Elevators were last modernized 4 years ago and are operating without deficiency. Windows and exterior doors are in fair condition; sealant replacement is recommended at selected locations. ADA observations include non-compliant slopes at two accessible routes and signage at parking; cost to cure is estimated at $467,000. Domestic water piping is copper and PVC with no evidence of widespread leakage. The roofing system exhibits localized ponding and sealant deterioration; spot repairs are recommended within 12 months.

FICTITIOUS SAMPLE DOCUMENT — all names, figures and entities are invented for classroom training use only

Construction Details

Average in-place rent is $1,279 per month against an average unit size of 973 square feet. Mechanical systems include rooftop package units and central plant equipment of varying age. The roof is a 31-year membrane system with an estimated remaining useful life of 4 years. Unit interiors feature quartz countertops, stainless appliances, in-unit washer and dryer and plank flooring in select renovated homes. Resident turnover has averaged 6.0% annually with renewal retention above 93.7%. The community offers a resort-style pool, fitness center, resident clubhouse, package lockers and a dog park.

Average in-place rent is $1,279 per month against an average unit size of 973 square feet. Cypress Commons was originally constructed in 1969 and consists of 416 apartment homes in a building of 8 stories. Life-safety systems include a fully sprinklered building, addressable fire alarm panel and emergency lighting. The roof is a 8-year membrane system with an estimated remaining useful life of 7 years.

Deferred Maintenance

The roofing system exhibits localized ponding and sealant deterioration; spot repairs are recommended within 12 months. Asphalt paving shows alligator cracking and should be sealcoated and restriped during the next 4 months. Elevators were last modernized 7 years ago and are operating without deficiency. ADA observations include non-compliant slopes at two accessible routes and signage at parking; cost to cure is estimated at $399,000. Domestic water piping is copper and PVC with no evidence of widespread leakage. Windows and exterior doors are in fair condition; sealant replacement is recommended at selected locations.

Windows and exterior doors are in fair condition; sealant replacement is recommended at selected locations. Asphalt paving shows alligator cracking and should be sealcoated and restriped during the next 31 months. Elevators were last modernized 7 years ago and are operating without deficiency. ADA observations include non-compliant slopes at two accessible routes and signage at parking; cost to cure is estimated at $138,000. Domestic water piping is copper and PVC with no evidence of widespread leakage. Electrical service is adequate for current demand; select panels are nearing the end of their useful life.

Improvements Description

Common area interiors have been refreshed within the last 10 years and are in average to good condition. Life-safety systems include a fully sprinklered building, addressable fire alarm panel and emergency lighting. The community offers a resort-style pool, fitness center, resident clubhouse, package lockers and a dog park. Resident turnover has averaged 3.4% annually with renewal retention above 91.5%. The roof is a 33-year membrane system with an estimated remaining useful life of 9 years.

Common area interiors have been refreshed within the last 9 years and are in average to good condition. Mechanical systems include rooftop package units and central plant equipment of varying age. Average in-place rent is $1,279 per month against an average unit size of 973 square feet. The structure is of wood-frame, masonry and steel-frame construction on a slab-on-grade foundation.

Deferred Maintenance

The roofing system exhibits localized ponding and sealant deterioration; spot repairs are recommended within 12 months. ADA observations include non-compliant slopes at two accessible routes and signage at parking; cost to cure is estimated at $376,000. Asphalt paving shows alligator cracking and should be sealcoated and restriped during the next 31 months. Elevators were last modernized 4 years ago and are operating without deficiency.

Asphalt paving shows alligator cracking and should be sealcoated and restriped during the next 20 months. Elevators were last modernized 4 years ago and are operating without deficiency. Domestic water piping is copper and PVC with no evidence of widespread leakage. Electrical service is adequate for current demand; select panels are nearing the end of their useful life. The roofing system exhibits localized ponding and sealant deterioration; spot repairs are recommended within 12 months.

Building Systems

The community offers a resort-style pool, fitness center, resident clubhouse, package lockers and a dog park. Exterior finishes comprise brick veneer, fiber-cement siding and aluminum storefront glazing in good condition. Resident turnover has averaged 12.8% annually with renewal retention above 95.1%. Average in-place rent is $1,279 per month against an average unit size of 973 square feet. Cypress Commons was originally constructed in 1969 and consists of 416 apartment homes in a building of 33 stories. Unit interiors feature quartz countertops, stainless appliances, in-unit washer and dryer and plank flooring in select renovated homes.

FICTITIOUS SAMPLE DOCUMENT — all names, figures and entities are invented for classroom training use only

Immediate Repairs and Replacement Reserve Schedule

System	Age (yrs)	EUL	RUL	Condition	Immediate	Reserve (10-yr)
Roof	18	31	13	Fair	$25,000	$223,000
Paving	20	20	0	Fair	$21,000	$226,000
HVAC	6	10	4	Fair	$37,000	$127,000
Plumbing	7	28	21	Fair	$24,000	$174,000
Electrical	9	29	20	Fair	$7,000	$52,000
Elevators	1	17	16	Fair	$18,000	$66,000
Fire/Life Safety	6	19	13	Fair	$3,000	$86,000
Windows	10	15	5	Fair	$21,000	$103,000
Siding/Facade	17	18	1	Good	$37,000	$11,000
Flooring	9	13	4	Fair	$18,000	$112,000
Appliances	7	21	14	Fair	$7,000	$64,000
Landscaping	1	28	27	Fair	$36,000	$121,000
Pool/Amenity	11	37	26	Good	$7,000	$214,000
Signage	4	33	29	Fair	$34,000	$27,000
Fencing	15	21	6	Fair	$6,000	$234,000
Roof (2)	15	30	15	Poor	$24,000	$91,000
Paving (2)	10	37	27	Fair	$8,000	$260,000
HVAC (2)	13	32	19	Fair	$25,000	$259,000
Plumbing (2)	13	20	7	Fair	$0	$80,000
Electrical (2)	1	11	10	Good	$16,000	$71,000
Elevators (2)	25	27	2	Fair	$32,000	$105,000
Fire/Life Safety (2)	15	20	5	Fair	$17,000	$116,000
Windows (2)	10	25	15	Poor	$39,000	$173,000
Siding/Facade (2)	9	35	26	Poor	$12,000	$109,000
Flooring (2)	2	13	11	Good	$4,000	$231,000
Appliances (2)	14	20	6	Good	$39,000	$235,000
Landscaping (2)	16	19	3	Fair	$8,000	$59,000
Pool/Amenity (2)	8	27	19	Fair	$27,000	$234,000
Signage (2)	13	18	5	Good	$36,000	$265,000
Fencing (2)	9	36	27	Fair	$16,000	$213,000

Report generated 12/23/2022. Figures are unaudited and subject to change.

FICTITIOUS SAMPLE DOCUMENT — all names, figures and entities are invented for classroom training use only

Findings and Opinions of Cost

Item	Location	Observed Condition	Recommended Action	Priority	Est. Cost
HVAC unit	Bldg B	Beyond useful life	Replace RTU	Year 1	$60,500
Handrail	Roof	Loose	Secure	Year 1	$74,000
Fire extinguishers	Site	Expired tags	Service	Immediate	$13,000
Window sealant	Bldg A	Failed	Re-caulk	Year 2-5	$25,500
Sidewalk	Roof	Trip hazards	Grind / replace	Year 1	$14,500
Handrail	Bldg A	Loose	Secure	Reserve	$12,000
Dumpster enclosure	Mechanical	Damaged gate	Repair	Immediate	$20,000
Sprinkler heads	Bldg A	Painted heads	Replace	Reserve	$42,000
Sidewalk	Roof	Trip hazards	Grind / replace	Immediate	$36,000
Sprinkler heads	Common	Painted heads	Replace	Reserve	$33,000
Sprinkler heads	Common	Painted heads	Replace	Year 2-5	$33,000
Asphalt paving	Mechanical	Alligator cracking	Mill and overlay	Year 1	$32,000
Fire extinguishers	Common	Expired tags	Service	Reserve	$60,500
Roof membrane	Common	Ponding / seams	Re-seal and repair	Year 2-5	$38,000
Asphalt paving	Common	Alligator cracking	Mill and overlay	Immediate	$66,500
HVAC unit	Common	Beyond useful life	Replace RTU	Year 1	$83,000
Sidewalk	Common	Trip hazards	Grind / replace	Year 1	$89,500
Roof membrane	Bldg B	Ponding / seams	Re-seal and repair	Immediate	$56,000
Stair treads	Bldg A	Worn / loose	Replace treads	Immediate	$21,500
Dumpster enclosure	Roof	Damaged gate	Repair	Reserve	$13,500
Sprinkler heads	Site	Painted heads	Replace	Year 1	$70,000
Dumpster enclosure	Bldg A	Damaged gate	Repair	Immediate	$24,500
HVAC unit	Bldg B	Beyond useful life	Replace RTU	Immediate	$66,000
Handrail	Roof	Loose	Secure	Immediate	$83,000
HVAC unit	Common	Beyond useful life	Replace RTU	Year 2-5	$41,500
Dumpster enclosure	Bldg A	Damaged gate	Repair	Immediate	$67,500
HVAC unit	Common	Beyond useful life	Replace RTU	Immediate	$54,000
Sidewalk	Mechanical	Trip hazards	Grind / replace	Reserve	$40,500
HVAC unit	Mechanical	Beyond useful life	Replace RTU	Immediate	$58,500
Stair treads	Bldg A	Worn / loose	Replace treads	Immediate	$65,000
HVAC unit	Mechanical	Beyond useful life	Replace RTU	Year 2-5	$15,500
Sprinkler heads	Site	Painted heads	Replace	Reserve	$8,000
Water heater	Site	Corrosion	Replace	Year 1	$82,500
Sidewalk	Bldg B	Trip hazards	Grind / replace	Year 1	$86,000
Handrail	Mechanical	Loose	Secure	Year 1	$67,500
Sprinkler heads	Bldg A	Painted heads	Replace	Year 1	$29,500
HVAC unit	Bldg B	Beyond useful life	Replace RTU	Immediate	$15,500
Roof membrane	Site	Ponding / seams	Re-seal and repair	Reserve	$72,500
Sidewalk	Roof	Trip hazards	Grind / replace	Year 1	$53,000
Asphalt paving	Bldg B	Alligator cracking	Mill and overlay	Reserve	$77,000

Report generated 12/23/2022. Figures are unaudited and subject to change.

FICTITIOUS SAMPLE DOCUMENT — all names, figures and entities are invented for classroom training use only

Recommendations

Domestic water piping is copper and PVC with no evidence of widespread leakage. Electrical service is adequate for current demand; select panels are nearing the end of their useful life. Elevators were last modernized 3 years ago and are operating without deficiency. Windows and exterior doors are in fair condition; sealant replacement is recommended at selected locations. Asphalt paving shows alligator cracking and should be sealcoated and restriped during the next 15 months.

Electrical service is adequate for current demand; select panels are nearing the end of their useful life. Elevators were last modernized 8 years ago and are operating without deficiency. Windows and exterior doors are in fair condition; sealant replacement is recommended at selected locations. Domestic water piping is copper and PVC with no evidence of widespread leakage. ADA observations include non-compliant slopes at two accessible routes and signage at parking; cost to cure is estimated at $206,000. The roofing system exhibits localized ponding and sealant deterioration; spot repairs are recommended within 12 months.

Deferred Maintenance

Windows and exterior doors are in fair condition; sealant replacement is recommended at selected locations. Asphalt paving shows alligator cracking and should be sealcoated and restriped during the next 20 months. The roofing system exhibits localized ponding and sealant deterioration; spot repairs are recommended within 12 months. Elevators were last modernized 10 years ago and are operating without deficiency. Domestic water piping is copper and PVC with no evidence of widespread leakage. Electrical service is adequate for current demand; select panels are nearing the end of their useful life.

Electrical service is adequate for current demand; select panels are nearing the end of their useful life. Asphalt paving shows alligator cracking and should be sealcoated and restriped during the next 18 months. ADA observations include non-compliant slopes at two accessible routes and signage at parking; cost to cure is estimated at $338,000. Elevators were last modernized 7 years ago and are operating without deficiency.

Deferred Maintenance

ADA observations include non-compliant slopes at two accessible routes and signage at parking; cost to cure is estimated at $266,000. Domestic water piping is copper and PVC with no evidence of widespread leakage. Electrical service is adequate for current demand; select panels are nearing the end of their useful life. Windows and exterior doors are in fair condition; sealant replacement is recommended at selected locations. Elevators were last modernized 8 years ago and are operating without deficiency.

Asphalt paving shows alligator cracking and should be sealcoated and restriped during the next 28 months. Elevators were last modernized 11 years ago and are operating without deficiency. Domestic water piping is copper and PVC with no evidence of widespread leakage. ADA observations include non-compliant slopes at two accessible routes and signage at parking; cost to cure is estimated at $8,000.

FICTITIOUS SAMPLE DOCUMENT — all names, figures and entities are invented for classroom training use only

Certification

I certify that, to the best of my knowledge and belief, the statements of fact contained in this report are true and correct and that I have no present or prospective interest in Cypress Commons and no personal interest with respect to the parties involved.

The analyses, opinions and conclusions are limited only by the reported assumptions and limiting conditions. The inspection of the property was performed on November 29, 2022.

_____

Chloe Walker, PE

Northbridge Inspection Services

FICTITIOUS SAMPLE DOCUMENT — all names, figures and entities are invented for classroom training use only